

4.1.2 Groundwater Analytical Results

Four groundwater samples were collected during the groundwater evaluation investigation. The groundwater samples were analyzed for total xylene using USEPA Method 8020. Total xylene was detected in three of the four groundwater samples. The concentrations of xylene ranged from not detected in Monitoring Well JLM032 to 220 micrograms per liter (ug/L) in Monitoring Well PZX-1. The xylene concentrations in the groundwater are illustrated on Figure 7. The groundwater analytical results are summarized in Table 3 and the laboratory analytical reports are contained in Appendix C.

4.2 QUALITY ASSURANCE/QUALITY CONTROL

Analytical results of the subsurface and groundwater samples collected during the Groundwater Evaluation Study were evaluated using the United States Environmental Protection Agency (USEPA) Contract Laboratory Program National Functional Guidelines for Organic Data Review (NFGO), (USEPA 1993). The quality assurance/quality control review included laboratory method blanks, trip blanks, matrix spike/matrix spike duplicates (MS/MSD), field duplicates, and equipment rinsate blanks.

The quality assurance/quality control results are listed below.

- Chain-of-Custody forms were signed by the relinquisher and reviewer.
- All analyses were performed as requested.
- All samples were analyzed within the required 14 day holding times.

- All laboratory method blanks for the sampling events contained no positive detections of the target analysis.
- No positive detections of the target analyte were reported in the rinsate blanks.
- There were no positive detections of the target analytes in the trip blanks.
- All surrogate percent recovery were within the required QC limits.

Based on the results of the quality assurance/quality control review, the data are valid for use (as qualified) in reporting the results of the investigation. The quality assurance/quality control review is presented in Appendix D.

* * * * *

5.0 CONCLUSION AND RECOMMENDATIONS

5.1 CONCLUSIONS

5.1.1 Subsurface Soil Sampling

A subsurface soil sample was collected from the north, south, east, and west sides of the Xylene Site. FPX was encountered in the Soil Boring JLM029, which is south of the Xylene Site within 25 feet of the pumping station. Soil Sample JLM029-1 indicated the presence of this FPH by the elevated levels of xylene (2,700,000 ug/kg) in the soil sample. Low concentrations of xylene (below 1300 ug/kg) were detected in Soil Samples JLM031-1 and JLM032-1, which are located to the east and north of the Xylene Site. Xylene was not detected in Soil Sample JLM030-1, which is located to the west of the Xylene Site.

5.1.2 Groundwater Sampling

FPX was encountered in Monitoring Wells JLM029, PZX-2, PZX-3, PZX-4, PZX-5, PZX-6, PZX-7, and PZX-8. These monitoring wells were not sampled because of the presence of FPX. In addition, Monitoring Well PZX-9 was not sampled because the screened interval is below the water table.

A groundwater sample was collected from Monitoring Wells JLM030, JLM031, JLM032 and PZX-1, and analyzed for total xylene. The concentration of xylene in the groundwater samples ranged from below detection limits (less than 2 ug/L) to 220 ug/L. These xylene concentrations are significantly below the USEPA MCL of 10 mg/L or 10,000 ug/L.

5.2 RECOMMENDATIONS

The results of the groundwater evaluation at the Xylene Site indicate that the approximate extent of the xylene associated with the xylene release has been defined. Therefore, no additional investigation activities are proposed for the Xylene Site.

In order to mitigate further migration of the FPX and increase the recovery of FPX , Amoco implemented the installation of the wellpoint/VRD recovery system. The wellpoint/VRD system was installed along the northern and western fencelines of the Xylene Site in order to provide gradient control and recover the FPX. The FPX is being used in conjunction with the existing recovery well (RWX-1) previously installed at the Xylene Site. The location of the wellpoint/VRD recovery system is illustrated on Figure 8.

Since the approximate extent of the xylene at the Xylene Site has been delineated and the wellpoint/VRD recovery system is in operation, no further action, with the exception of the recovery system operation and maintenance, is recommended.

* * * * *

6.0 REFERENCES

Burns & McDonnell Waste Consultants, Inc., December 1995, Groundwater Evaluation Study Plan for the Amoco Pipeline Xylene Site, Amoco Corporation, Hammond, Indiana.

United States Environmental Protection Agency (USEPA), 1988, Guidance for Conducting Remedial Investigations and Feasibility Studies Under CERCLA, Interim Final, USEPA/540/6-89/004, OSWER Directive 9355.3-01.

United States Environmental Protection Agency (USEPA), 1986, Test Methods for Evaluating Solid Waste, Third Edition, as amended by Update I (Federal Register, August 31, 1993), SW-846.

Watson, L.R., Shedlock, R.J., Banaszak, K.J., Arihood, L.D., Doss, P.K., 1989, Preliminary Analysis of the Shallow Groundwater System in the Vicinity of the Grand Calumet River/Indiana Harbor Canal, Northwestern Indiana: U.S. Geological Survey Open-File Report 88-492, 45 p.

* * * * *

TABLES

Table 1
Relative Groundwater Elevations
Amoco Xylene Site
Hammond, Indiana

Monitoring Well Location	Date	TOC MSL (ft.)	Depth to Product (ft.)	Depth to Groundwater (ft.)	Corrected Groundwater Elevation (ft.)	Total Depth (ft.)
PZX-1	05/07/96	588.06	trace	5.08	582.98	16.83
	05/08/96		trace	5.05	583.01	16.83
PZX-2	05/07/96	588.16	4.92	5.56	583.16*	19.41
	05/08/96		4.95	5.53	583.13*	19.41
PZX-3	05/07/96	587.53	4.35	6.38	582.92*	18.40
	05/08/96		4.35	6.33	582.92*	18.40
PZX-4	05/07/96	585.43	2.32	6.95	582.51*	17.50
	05/08/96		2.28	7.05	582.53*	17.50
PZX-5	05/07/96	583.75	0.95	1.03	582.79*	16.15
	05/08/96		0.94	1.00	582.80*	16.15
PZX-6	05/07/96	585.46	2.46	8.26	582.25*	13.76
	05/08/96		2.49	8.32	582.21*	13.76
PZX-7	05/07/96	585.00	1.96	4.66	582.69*	17.28
	05/08/96		1.98	4.65	582.67*	17.28
PZX-8	05/07/96	588.15	4.66	5.75	583.35*	20.03
	05/08/96		4.69	5.77	583.32*	20.03
PZX-9	05/07/96	585.68	—	3.67	582.02	NM
	05/08/96		—	3.63	582.05	NM
JLM029	05/07/96	585.64	2.74	3.16	582.85*	11.04
	05/08/96		2.74	3.88	582.75*	13.10
JLM030	05/07/96	584.75	—	1.21	583.54	10.20
	05/08/96		—	1.38	583.37	14.15
JLM031	05/07/96	584.84	trace	1.87	582.97	14.40
	05/08/96		trace	1.92	582.92	16.25
JLM032	05/07/96	583.65	—	0.95	582.70	12.60
	05/08/96		—	0.91	582.74	15.91

Notes:

— = Not measurable with interface probe.

* Groundwater elevations adjusted for presence of product using:

$$Z_{aw} = (1 - r_p)Z_{pw} + r_p Z_{ap}$$

Z_{aw} = Corrected elevation of air/water interface

r_p = Density of product (0.83 for diesel)

Z_{pw} = Elevation of product/water interface

Z_{ap} = Elevation of air/product interface

Table 2
Soil Analytical Results
Amoco Xylene Site
Hammond, Indiana

Sample No.	Date Sampled	Depth Sampled (ft)	Total Xylenes (µg/kg)
JLM029	5-1-96	1 to 3	2,700,000
TB	5-1-96	NA	U (2)
JLM030-1	5-2-96	2 to 4	U (2)
JLM031-1	5-2-96	1 to 3	320
JLM031-6	5-2-96	1 to 3	460
JLM031-ERB	5-2-96	NA	U (2)
TB5296	5-2-96	NA	U (2)
JLM032-1	5-3-96	1 to 3	1300 E
JLM032-1	5-3-96	1 to 3	630
TB5396	5-3-96	NA	U (2)

µg/kg = Micrograms per kilogram

NA = Not applicable

U (2) = Not detected above practical quantitation limit (PQL)

E = Concentration reported for this compound exceeds the calibration range of the instrument

JLM031-6 is a duplicate of JLM031-1.

Note: Sample JLM032 was not homogeneous and therefore, was analyzed twice.

Sample JLM031-ERB is a equipment rinsate blank of the decontaminated split spoon from Sample JLM031-1.

Table 3
Groundwater Analytical Results
Amoco Xylene Site
Hammond, Indiana

Sample No.	Date Sampled	Total Xylenes (µg/L)
MW-JLM030 GW-1	5-8-96	53
MW-PZX0 GW-1	5-8-96	52
MW-JLM031 GW-1	5-8-96	110
MW-JLM32 GW-1	5-8-96	U (2)
MW-PZX1 GW-1	5-8-96	220
MW-JLM031 GW-ERB	5-8-96	U (2)
TB 5-8-96	5-8-96	U (2)

µg/L = Micrograms per liter

U (2) = Not detected above the practical quantitation limit (PQL)

TB = Trip blank

Note: MW-PZX0 GW-1 is a duplicate of MW-JLM030 GW-1.

MW-JLM031 GW-ERB is a equipment rinsate of a disposal bailer.

FIGURES

K:\AMOCO\WHITING\WCI\AO\XYLENE\2XYLWP.DWG 6-17-96

LEGEND

- SOIL BORING LOCATION
- EXISTING RECOVERY WELL LOCATION
- △ EXISTING MONITORING WELL LOCATION
- ⊙ NEWLY INSTALLED MONITORING WELL LOCATION
- PL PIPE LINE
- G GAS
- OH OVERHEAD UTILITIES
- W WATER LINE

CALUMET AVENUE

DITCH

S-80A
△

S-59A
△
S-59B
△

BEAUTIFICATION WALL

OFFICE

CALUMET
WAREHOUSE

129TH STREET

JLM032

PZX-1
△

△ PZX-1

△ PZX-3

PZX-2
△

PZX-7
△

PZX-6
△

PZX-9
△

RWX-1
□

PZX-4
△

△ PZX-8

JLM029

JLM029A

JLM031

RECOVERY SYSTEM BUILDING

FENCE

XYLENE
PUMPHOUSE



Burns
&
McDonnell
Waste
Consultants,
Inc.


Figure 2
UTILITY LOCATION MAP
AMOCO XYLENE SITE
HAMMOND, INDIANA

LEGEND

- SOIL BORING LOCATION
- EXISTING RECOVERY WELL LOCATION
- △ EXISTING MONITORING WELL LOCATION
- ⊙ NEWLY INSTALLED MONITORING WELL LOCATION
- A-A' LINE OF GEOLOGIC CROSS SECTION

CALUMET AVENUE


DITCH



Burns
&
McDonnell
Waste
Consultants,
Inc.

Figure 3
SITE MAP
XYLENE AREA
WHITING REFINERY
WHITING, INDIANA

KS AMOCO WITTING NOT NO XYLENE VANS DWS 8-17-98



LEGEND

- SOIL BORING LOCATION
- EXISTING RECOVERY WELL LOCATION
- △ PZX-1
583.01
EXISTING MONITORING WELL LOCATION
AND GROUNDWATER ELEVATION IN FEET ABOVE
MEAN SEA LEVEL
- JLM032
582.74
NEWLY INSTALLED MONITORING WELL LOCATION
AND GROUNDWATER ELEVATION IN FEET ABOVE
MEAN SEA LEVEL

CALUMET AVENUE

DITCH

129TH STREET

BEAUTIFICATION WALL

OFFICE

XYLENE
PUMPHOUSE

RECOVERY SYSTEM BUILDING

FENCE

CALUMET
WAREHOUSE

NOTE: GROUNDWATER ELEVATIONS FOR MONITORING WELLS JLM029, AND PZX-1 THROUGH PZX-8
WERE CORRECTED FRO THE PRESENCE OF FREE PHASE XYLENE.



**Burns
&
McDonnell
Waste
Consultants
Inc.**

Figure 5
**GROUNDWATER
ELEVATION MAP**
MAY 8, 1996
**AMOCO XYLENE SITE
HAMMOND, INDIANA**


LEGEND

- SOIL BORING LOCATION
- EXISTING RECOVERY WELL LOCATION
- △ EXISTING MONITORING WELL LOCATION
- JLM031
320 @ 1-3 FT. NEWLY INSTALLED MONITORING WELL LOCATION WITH XYLENE CONCENTRATION IN MICROGRAMS PER KILOGRAM AND DEPTH OF SAMPLE IN FEET
- U(2) = NOT DETECTED ABOVE THE PRACTICAL QUANTITATION LIMIT
- E = THE CONCENTRATION REPORTED FOR THIS COMPOUND EXCEEDS THE CALIBRATION RANGE OF THE INSTRUMENT

CALUMET AVENUE

DITCH

129TH STREET



NOTE: SAMPLE JLM032-1 WAS NOT HOMOGENEOUS, THEREFORE THE SAMPLE WAS ANALYZED TWICE.

**Burns
&
McDonnell
Waste
Consultants,
Inc.**

Figure 6
**XYLENE
CONCENTRATIONS
IN SOIL
AMOCO XYLENE SITE
HAMMOND, INDIANA**


K:\AMOCO\WHITING\WCI\AO\XYLENE\2XYLWP.DWG 6-17-96

LEGEND

- SOIL BORING LOCATION
- PZX-1 □ EXISTING RECOVERY WELL LOCATION
- 220 △ EXISTING MONITORING WELL LOCATION WITH XYLENE CONCENTRATION IN MICROGRAMS PER LITER
- JLM 030 53 ● NEWLY INSTALLED MONITORING WELL LOCATION WITH XYLENE CONCENTRATION IN MICROGRAMS PER LITER.
- FPX FREE PHASE XYLENE
- U(2) = NOT DETECTED ABOVE PRACTICAL QUANTITATION LIMITS

CALUMET AVENUE

DITCH



NOTE: MONITORING WELLS DENOTED WITH FPX WERE NOT SAMPLED DUE TO PRESENCE OF FREE PHASE XYLENE.

Burns
&
McDonnell
Waste
Consultants
Inc.

Figure 7
XYLENE
CONCENTRATION
IN GROUNDWATER
AMOCO XYLENE SITE
HAMMOND, INDIANA

K:\AMOCO\WHITING\WCI\AO\XYLENE\2XYLWP.DWG 6-17-96

LEGEND


- SOIL BORING LOCATION
- EXISTING RECOVERY WELL LOCATION
- △ EXISTING MONITORING WELL LOCATION
- ⊙ NEWLY INSTALLED MONITORING WELL LOCATION

WP-30 ○ WELLPOINT/VRD WELL

CALUMET AVENUE

DITCH

129TH STREET



Burns
&
McDonnell
Waste
Consultants
Inc.

Figure 8
WELLPOINT/VRD
RECOVERY SYSTEM
LOCATION
AMOCO XYLENE SITE
HAMMOND, INDIANA

APPENDIX A
DRILLING LOGS

Drilling Log

Project Name <i>Amoco Xylene</i>		Project Number <i>95-465-4-501</i>		Boring Number <i>JLM029A</i>	
Ground Elevation <i>NM</i>		Location <i>South of Pumping Station</i>		Page <i>1</i> of <i>1</i>	
Air Monitoring Equipment <i>OVM 580B & MSA 360</i>				Total Footage <i>10'</i>	
Drilling Type <i>HSA</i>	Hole Size <i>4.25 I.D.</i>	Overburden Footage <i>10.0</i>	Bedrock Footage <i>0</i>	No. Of Samples <i>4</i>	No. Of Core Boxes <i>0</i>
Drilling Company <i>Fox Drilling</i>			Driller (s) <i>Gary Vockey</i>		
Drilling Rig <i>ATV - CME 55</i>			Type of Sampler <i>Split Spun 2" x 2'</i>		
Date <i>5/1/96</i>		To <i>5/1/96</i>		Field Observer (s) <i>Scott Koib</i>	

Depth (feet)	Description	Class	Blow Count	Recov.	Run/Time	Sample Desig.	PID (ppm)			Remarks/ Water Levels
							BZ	BH	S	
	Asphalt on surface.									Start 8:45a
1	Topsoil, dark brown.		<i>11/17</i>				<i>0</i>	<i>0</i>	<i>4.8</i>	PID
2	SAND, fine to medium, a little c-sand black, strong petroleum odor		<i>56 for 5"</i>	<i>16/18</i>		<i>1</i>	<i>0</i>	<i>2</i>		LEL
3	SAND, fine to medium, black, strong petroleum odor		<i>10/8</i>	<i>26/24</i>		<i>2</i>	<i>0</i>	<i>2.1</i>	<i>7384</i>	PID
4			<i>7/6</i>				<i>0</i>			LEL
5							<i>SS</i>	<i>124</i>	<i>ppm</i>	
6	SAND, medium to coarse, black wet, strong petroleum odor		<i>3/4</i>			<i>3</i>	<i>0</i>	<i>24</i>	<i>2170</i>	PID
7			<i>3/4</i>				<i>0</i>	<i>1</i>		LEL
8							<i>SS</i>	<i>80</i>	<i>ppm</i>	
9			<i>3/5</i>			<i>4</i>	<i>0.5</i>	<i>62</i>	<i>1380</i>	PID
10			<i>7/7</i>				<i>0</i>	<i>NM</i>	<i>NM</i>	LEL
11							<i>SS - NM</i>			
12	Total Depth 10.0'									9:15a completed
13										Backfilled
14										boring with bentonite to 0.5 feet. Asphalt to surface.

BZ=Breathing Zone BH=Bore Hole S=Sample

Burns & Consultants, Inc.

Form WCI-OP2-1

Drilling Log

Project Name Amoco - Xylene		Project Number 95-465-4-501		Boring Number JLM 029	
Ground Elevation 585.97		Location South of Xylene Pumping Station		Page 1 of 2	
Air Monitoring Equipment OVM 580B & MSA 360				Total Footage 18.0	
Drilling Type HSA	Hole Size 4.25" I.D.	Overburden Footage 18.0	Bedrock Footage 0	No. Of Samples 5	No. Of Core Boxes 0
Drilling Company For Drilling			Driller (s) Cary Yockey		
Drilling Rig ATV CME 55			Type of Sampler Split Spoon 2"		
Date 0945 5/1/96		To 1130 5/1/96		Field Observer (s) Scott Kolb	

Depth (feet)	Description	Class	Blow Count	Recov.	Run/Time	Sample Desig.	PID (ppm)			Remarks/ Water Levels
							BZ	BH	S	
1	Asphalt on Surface.									Started 9:45a
2	Topsoil, dark brown		17							
2	SLAG, strong Petroleum odor		50 for 3"			1	0	Nm	2803	PID (ppm)
3	-----									Split Spoon (SS) - 25 ppm
4	SAND, medium to coarse, black strong petroleum odor		5/7/5/23	12/24		2	0.5	20.4	3407	PID (ppm)
5							0	0	Nm	LEL (%)
6	SAND, medium to coarse, black strong petroleum odor		12/6/6/4	16/24		3	0	60	342	PID (ppm)
7							0	0	Nm	LEL (%)
8										
9										
10										
11	SAND, fine to medium, grey wet		3/5/6/12	18/24		4			1107	PID (ppm)
12							0	160	870	PID (ppm)
13							0	0		LEL (%)
14										

BZ=Breathing Zone BH=Bore Hole S=Sample

Burns & Consultants, Inc.

Drilling Log Continuation

Project Name <i>Amoco - Xylene</i>							Boring Number <i>JLM029</i>			
Project Number <i>95-465-4-501</i>							Page <i>2</i> of <i>2</i>			
							Date <i>5/1/96</i>			
Depth (feet)	Description	Class	Blow Count	Recov.	Run/ Time	Sample Desig.	PID (ppm)			Remarks/ Water Levels
							BZ	BH	S	
15	<i>SAND, fine, grey, wet.</i>									
16						<i>5</i>	<i>0 96</i>	<i>104.4</i>	<i>PID (ppm)</i>	
17							<i>0 0</i>	<i>Nm</i>	<i>LEL (%)</i>	
18							<i>SS - 2.1</i>			
18	<i>Total Depth @ 18.0'</i>									<i>Completed @ 11:30a</i>
19										<i>Installed 15'</i>
20										<i>of 2" stainless</i>
21										<i>steel screen</i>
22										<i>(10 slot) to</i>
23										<i>a depth of</i>
24										<i>17.0' River</i>
25									<i>to surf.</i>	
										<i>Gravel packed</i>
										<i>to 1.8 feet</i>
										<i>egg. bantam</i>
										<i>pebbles to</i>
										<i>0.8 ft. egg.</i>
										<i>Conant to</i>
										<i>surface.</i>
										<i>Grouted</i>
										<i>protective</i>
										<i>cover & flush</i>
										<i>Finished well</i>
										<i>@ 3:00p</i>

BZ=Breathing Zone BH=Bore Hole S=Sample

Burns & McDonnell Inc. Waste Consultants, Inc.

Drilling Log

Project Name <u>Amoco Xylene.</u>		Project Number <u>95-465-4-501</u>		Boring Number <u>JLM 030</u>	
Ground Elevation <u>584.86</u>		Location <u>West of Pumping Station</u>		Page <u>1</u> of <u>2</u>	
Air Monitoring Equipment <u>OMM 580B & MSA 360</u>				Total Footage <u>18</u>	
Drilling Type	Hole Size	Overburden Footage	Bedrock Footage	No. Of Samples	No. Of Core Boxes
<u>HSA</u>	<u>4.25" ID</u>	<u>18.0</u>	<u>0</u>	<u>5</u>	<u>0</u>
Drilling Company <u>Fox Drilling</u>			Driller (s) <u>Gary Yockey</u>		
Drilling Rig <u>ATV CME 55</u>			Type of Sampler <u>Split Spoon</u>		
Date <u>5/2/96 7:30</u> To <u>5/2/96</u>			Field Observer (s) <u>Scott Kolb</u>		

Depth (feet)	Description	Class	Blow Count	Recov.	Run/Time	Sample Desig.	PID (ppm)			Remarks/ Water Levels
							BZ	BH	S	
1	Asphalt on Surface.									Start @ 7:15a
2	Topsoil.	<u>7</u> <u>30</u>	<u>7</u> <u>30</u>	<u>9</u> <u>12</u>		<u>1</u>	<u>0</u>	<u>Nm</u>	<u>12.6</u>	PID
3	SLAB									
4	SAND, fine, black, wet, petroleum odor.		<u>5</u> <u>7</u> <u>7</u> <u>7</u>	<u>15</u> <u>24</u>		<u>2</u>	<u>0</u>	<u>Nm</u>	<u>273</u>	PID
5										
6	SAND, medium to coarse, black, wet, petroleum odor		<u>2</u> <u>1</u> <u>2</u> <u>1</u>	<u>10</u> <u>24</u>		<u>3</u>	<u>0</u>	<u>14</u>	<u>62.4</u>	PID
7									<u>5.5 - 12 ppm</u>	
8										
9										
10										
11	SAND, fine to medium, grey, wet		<u>6</u> <u>5</u> <u>5</u> <u>9</u>	<u>16</u> <u>24</u>		<u>4</u>	<u>0</u>	<u>9.4</u>	<u>12.0</u>	PID
12							<u>0</u>	<u>0</u>	<u>Nm</u>	LEZ
13							<u>35.</u>	<u>- 0. ppm</u>		
14										

BZ=Breathing Zone BH=Bore Hole S=Sample

Drilling Log Continuation

Project Name <u>Amoco Xylene</u>							Boring Number <u>SLM 030</u>				
Project Number <u>95-465-4-501</u>							Page <u>2</u> of <u>2</u>				
							Date <u>5/2/96</u>				
Depth (feet)	Description	Class	Blow Count	Recov.	Run/ Time	Sample Desig.	PID (ppm)			Remarks/ Water Levels	
							BZ	BH	S		
15	SAND, fine to medium, grey, wet										
16			$\frac{4}{9}$	$\frac{24}{24}$			5	0	4.0	6.1	PID (ppm)
17			$\frac{9}{9}$	$\frac{24}{24}$				0	0	NM	LEL (0%)
18	Total Depth @ 18.0'									SS. 0 ppm	
										Stopped 9:00am Installed 15' Stainless steel screen to 16.3' Rise to surf. Screen was 10-slot Gravel pack to 1.5 ft 1' bentonite pellets. cement to surf. Flush man cover. Completed 10:30 PM	

BZ=Breathing Zone BH=Bore Hole S=Sample

Burns
&
McDonnell
Waste
Consultants
Inc.

Drilling Log

Project Name Amoco - Xylene		Project Number 95-465-4-501		Boring Number JLm 031	
Ground Elevation 585.21		Location East of Pumping Station		Page 1 of 2	
Air Monitoring Equipment DVM 580B & MSA 361				Total Footage 18'	
Drilling Type	Hole Size	Overburden Footage	Bedrock Footage	No. Of Samples	No. Of Core Boxes
HSA	4.25" I.D.	18.0	0	5	0
Drilling Company Fox Drilling			Driller (s) Gary Yockey		
Drilling Rig ATV CME55			Type of Sampler Split Spoon 2"		
Date 5/2/96		To 5/3/96 9:30		Field Observer (s) Scott Kolb	

Depth (feet)	Description	Class	Blow Count	Recov.	Run/Time	Sample Desig.	PID (ppm)			Remarks/ Water Levels
							BZ	BH	S	
1	Gravel on Surface									
2	Topsoil, brown SAND, medium, black		$\frac{2}{5}$ $\frac{7}{9}$	$\frac{16}{24}$		1	0	0.9	114.1	PID LEL
3	SAND, medium, black, wet, petroleum odor		$\frac{1}{1}$ $\frac{11}{9}$	$\frac{16}{24}$		2	Nm	Nm	354	PID LEL
4	SAND, fine to medium, black, very wet - strong petroleum odor		$\frac{4}{3}$ $\frac{1}{1}$	$\frac{12}{24}$		3	0	6.4	1004	PID LEL
5							S.S.	13.3	ppm	
6							0	17.8	12.6	PID
7							0	0	Nm	LEL
8							S.S.	16.4	ppm	
9										
10										
11	SAND, fine, greyish black, wet petroleum odor (odor not the same as in JLm 029 & JLm 030)		$\frac{3}{7}$ $\frac{9}{8}$			4	0	0	Nm	LEL
12							S.S.	1.6		
13										
14										

BZ=Breathing Zone BH=Bore Hole S=Sample

Drilling Log Continuation

Project Name <u>Amoco Xylene</u>							Boring Number <u>JLM 031</u>			
Project Number <u>95-465-4-501</u>							Page <u>2</u> of <u>2</u>			
							Date <u>5/3/96</u>			
Depth (feet)	Description	Class	Blow Count	Recov.	Run/ Time	Sample Desig.	PID (ppm)			Remarks/ Water Levels
							BZ	BH	S	
15	SAND, fine to medium, grey, wet		<u>11</u>							
16			<u>9</u>	<u>24</u>						
17			<u>11</u>	<u>24</u>						
18			<u>15</u>							
19	Total Depth @ 18.0'									
20										
										Completed 8:45 a
										Installed 15' of 2"
										10-56+
										screen-
										stainless
										steel to
										170. Riser
										to surf.
										Gravel pack
										to 1.75
										1' bentonite
										pellets
										Cement to
										surf.
										Flush mount
										cover.
										Completed
										9:45 a

BZ=Breathing Zone BH=Bore Hole S=Sample

Drilling Log

Project Name Ameco Xylene		Project Number 95-465-4-501		Boring Number JLM-032	
Ground Elevation 583.81		Location North of Pumping Station		Page 1 of 2	
Air Monitoring Equipment DVM 580B & MSA 361				Total Footage 19'	
Drilling Type HSA	Hole Size 4.25' I.D.	Overburden Footage 19.0	Bedrock Footage 0	No. Of Samples 5	No. Of Core Boxes 0
Drilling Company Fox Drilling			Driller (s) Gary Yockey		
Drilling Rig ATV CME 655			Type of Sampler Split Spear 2"		
Date 5/3/96 9:30 To 5/3/96			Field Observer (s) Scott Kallb		

Depth (feet)	Description	Class	Blow Count	Recov.	Run/Time	Sample Desig.	PID (ppm)			Remarks/ Water Levels
							BZ	BH	S	
1	Gravel on Surface									Start @ 9:30
2	SLAG, blue & white		12 16 19 21	24 24		1	0	1.3	84.0	PID (ppm)
3								5.5	1.3	PID (ppm)
4										
5	SAND, medium, grey, wet		6 5 1 2	9 24		2	0	1.3	39.1	PID
6								SS - Nm		PID
7			3 1 6 8	12 24		3	0	12.3	1.3	PID
8							0	4	Nm	LEC
9							SS - 0			PID
10										
11	SAND, fine to medium, grey, wet		2 1 3 4	14 24		4	0	5.8	0.9	PID
12							0	0	Nm	LEC
13							SS - 1.3			
14										

BZ=Breathing Zone BH=Bore Hole S=Sample

Drilling Log Continuation

Project Name <u>Amoco Xylene</u>							Boring Number <u>JLM 032</u>			
Project Number <u>95-465-4-501</u>							Page <u>2</u> of <u>2</u>			
							Date <u>5/3/96</u>			
Depth (feet)	Description	Class	Blow Count	Recov.	Run/ Time	Sample Desig.	PID (ppm)			Remarks/ Water Levels
							BZ	BH	S	
15	SAND, fine to medium, grey, wet									
16			$\frac{3}{4}$ $\frac{9}{14}$	$\frac{21}{24}$		5-	0	0.9	0	PID
17							0	0	Nm	LEC
18							SS=	0.0	PID	
19	Total Depth @ 19.0'									
20										
<p>Completed drilling at 11:30a. Installed 15' of 2" stainless Steel Screen to a depth 17.0'. Riser to surface. Sand pack to 1.67' bgs. 1' bentonite pellets. Grout cement to surface. Installed protective surface casing. Completed well 12:45</p>										

BZ=Breathing Zone BH=Bore Hole S=Sample

APPENDIX B

**MONITORING WELL
CONSTRUCTION DIAGRAMS**

LOCKING WATERTIGHT CAP

STEEL PROTECTIVE COVER

SURFACE
ELEVATION 585.97 FT.

TOP OF PIPE (T.O.P.)
ELEVATION 585.64 FT.

STAINLESS STEEL
CASING

1.67 FT.

2.0 INCH DIAMETER
STAINLESS STEEL
CASING WITH FLUSH
THREADED COUPLINGS

0.8 FT. CEMENT GROUT

1.0 FT. BENTONITE PELLETS

NO. 10
SLOTTED SCREEN
0.010 INCH OPENINGS

3.16 FT FROM T.O.P.
WATER LEVEL
MEASURED

LENGTH OF
SCREEN

15.0 FT.

15.2 FT. SILICA SAND
WELL PACK

BOTTOM OF
WELL 17.0 FT.
BELOW GRADE

DATE INSTALLED 5-1-96


NOT TO SCALE

**Burns
&
McDonnell
Waste
Consultants
Inc.**

**MONITORING WELL
JLM029
CONSTRUCTION DIAGRAM**

LOCKING WATERTIGHT CAP
STEEL PROTECTIVE COVER

SURFACE
ELEVATION 584.86 FT.
TOP OF PIPE (T.O.P.)
ELEVATION 584.75 FT.



DATE INSTALLED 5-2-96


NOT TO SCALE

**Burns
&
McDonnell
Waste
Consultants,
Inc.**

**MONITORING WELL
JLM030
CONSTRUCTION DIAGRAM**

LOCKING WATERTIGHT CAP
STEEL PROTECTIVE COVER

SURFACE
ELEVATION 585.21 FT.
TOP OF PIPE (T.O.P.)
ELEVATION 584.84 FT.




NOT TO SCALE

**Burns
&
McDonnell
Waste
Consultants,
Inc.**

**MONITORING WELL
JLM031
CONSTRUCTION DIAGRAM**

LOCKING WATERTIGHT CAP
STEEL PROTECTIVE COVER

SURFACE
ELEVATION 583.81 FT.
TOP OF PIPE (T.O.P.)
ELEVATION 583.65 FT.



NOT TO SCALE

**Burns
&
McDonnell
Waste
Consultants,
Inc.**

**MONITORING WELL
JLM032
CONSTRUCTION DIAGRAM**

APPENDIX C

LABORATORY ANALYTICAL RESULTS



IEA

An Aquarion Company

126 West Center Court
Schaumburg, Illinois 60195

Phone 1-800-933-2580
Fax 847-705-1567

May 25, 1996

Burns & McDonnell
Scott Kolb
999 Oakmont Plaza Drive

Westmont, IL 60559

Dear Scott Kolb:

Please find enclosed the analytical results of the samples received at our laboratory on May 02, 1996. This report contains sections addressing the following information at a minimum:

- Definitions
- Analytical Methodology
- State certifications
- Analytical Results
- Chain-of-custody (if applicable)

IEA Project#: L72960720

Client Project: 95-465-4-50

Purchase Order#:

IEA Quote#:

Site:

Copies of this analytical report and supporting data are maintained in our files for three years; samples are retained for two weeks unless special arrangements have been made. Unless specifically indicated, all analytical testing was performed at this laboratory and no portion of the testing was subcontracted.

We appreciate your selection of our services and welcome any questions or suggestions you may have relative to this report. Please contact Jim Dowse at (800) 933-2580 for any additional information. Thank you for utilizing our services, we hope you will consider us for your future analytical needs.

I have reviewed and approved the enclosed data for final release.

Sincerely

Larry D. Lewis
Director of Operations
IEA-Illinois Laboratory

Monroe,
Connecticut
203-261-4468

N. Billerica,
Massachusetts
508-667-1400

Whippany,
New Jersey
201-428-8181

Cary,
North Carolina
919-677-0090



Printed on recycled paper



IEA

An Aquarion Company

Definitions of Data Qualifiers

Organic Analysis

- B - This analyte was detected in the method blank associated with this sample. The concentration reported in the method blank is suspected to contribute to the reported concentration of the analyte in the sample.
- E - The concentration reported for this compound exceeds the calibration range of the instrument.
- H - This sample had one or more surrogate recoveries above the acceptance criteria due to coelution with a nontarget compound.
- J - The reported concentration for this compound is an estimated value. When associated with tentatively identified compounds (TICs), the result is quantitated based on a response factor of 1. When the flag is associated with a calibrated target compound, the compound has been positively identified and the reported concentration is above the method detection limit (MDL), but below the practical quantitation limit (PQL).
- L - This sample had one or more surrogate recoveries below the acceptance criteria due to matrix effects. This effect was confirmed through a second analysis of the sample.
- LI - The recovery of the internal standard corresponding to this compound did not meet the acceptance criteria due to matrix effects. This effect was confirmed through a second analysis of the sample.
- T1 - The chromatographic profile of this sample does not match that of a gasoline standard. Another unidentifiable petroleum product is present in this sample. Quantitation is based on a gasoline standard calibration.
- T2 - The chromatographic profile of this sample does not match that of a diesel fuel standard. Another petroleum product is present in this sample. Quantitation is based on a diesel fuel standard calibration.
- U - This compound was not detected in the sample above the PQL.
- UD - This compound was not detected above the elevated PQL in this diluted analysis.

Inorganic Analysis

- E - The reported value was estimated due to the presence of interference.
- M - Duplicate injection precision was not met.
- N - Spiked sample recovery was not within control limits.
- S - The reported value was determined by the Method of Standard Additions(MSA).
- W - Post digestion spike for Furnace AA analysis is out of control limits (85-115%), while sample absorbance is less than 50% of spike absorbance.
- * - Duplicate analysis was not within control limits.
- + - Correlation Coefficient for the MSA is less than 0.995.





IEA

An Aquarion Company

Sample Summary

IEA-Illinois
Laboratory ID Client ID

L72960720-001
L72960720-002

JLM029
TB



**IEA**

An Aquarion Company

Client: Burns & McDonnell

IEA Job#: L72960720

Project ID: 95-465-4-50

Matrix: Soil

Method: 8020A

Purgeable Aromatic Compounds--BTEx
GC Volatiles Analysis
µg/Kg - Dry Weight

Percent Solids	81%	100%				PQL
Dilution Factor	10000	1				
Method Blank	VV050796	VV050796				
Client ID	JLM029	Method Blank				
Analyte Lab ID	001	VV050796				
Total Xylenes	2700000	U				2
Surrogate Recovery	98%	91%				65-135 %
Date Sampled	5/1/96	---				
Date Analyzed	5/7/96	5/7/96				

PQL = Practical Quantitation Limit

To obtain the sample-specific quantitation limit, multiply the PQL by the Dilution Factor.



**IEA**

An Aquarion Company

Client: Burns & McDonnell

IEA Job#: L72960720

Project ID: 95-465-4-50

Matrix: Water

Method: 8020A

Purgeable Aromatic Compounds--BTEX
GC Volatiles Analysis
µg/L

Dilution Factor	1	1				PQL
Method Blank	VV050796	VV050796				
Client ID	TB	Method Blank				
Analyte Lab ID	002	VV050796				
Total Xylenes	U	U				2
Surrogate Recovery	92%	91%				75-125%
Date Sampled	5/1/96	---				
Date Analyzed	5/8/96	5/7/96				

PQL = Practical Quantitation Limit

To obtain the sample-specific quantitation limit, multiply the PQL by the Dilution Factor.

Purgeable Aromatics--Xylenes

Matrix Spike/Matrix Spike Duplicate

Matrix: Soil

Date Analyzed: 5/7/96

IEA Sample ID: BATCH MS

Compound	Spike Added (ug/Kg)	Sample Concentration (ug/Kg)	Matrix Spike Concentration (ug/Kg)	% Recovery
Total Xylenes	150	<2	97	65%

Compound	Spike Added (ug/Kg)	Matrix Spike Dup Concentration (ug/Kg)	% Recovery	% Difference
Total Xylenes	150	105	70%	8%

% Recovery Limits: 65-135 %

% Difference Limits: +/- 20 %

Purgeable Aromatics--Xylenes

Matrix Spike/Matrix Spike Duplicate

Matrix: Water

Date Analyzed: 5/7/96
IEA Sample ID: BATCH QC

Compound	Spike Added (ug/L)	Sample Concentration (ug/L)	Matrix Spike Concentration (ug/L)	% Recovery
Total Xylenes	150	<2	153	102%

Compound	Spike Added (ug/L)	Matrix Spike Dup Concentration (ug/L)	% Recovery	% Difference
Total Xylenes	150	153	102%	0%

% Recovery Limits: 75-125%
% Difference Limits: +/- 20 %

Response Factor Report GC

Method : K:\CHEMSTN\GCV\METHODS\PVOC SOIL.M
 Title : PVOC in Soil; Calib. Date: 5/7/96
 Last Update : Tue May 14 13:26:55 1996
 Response via : Initial Calibration

Calibration Files

2ppb =GCV5853.D 5 =GCV5854.D 10 =GCV5855.D
 50 =GCV5856.D 100 =GCV5857.D

RT	Compound	2ppb	5	10	50	100	Avg RF	%RSD
1)2.27	MTBE	572.5	519.8	343.0	456.7	399.6	458.3 E3	19.98
2)3.98	BENZENE	1.3	1.2	1.2	1.2	1.2	1.2 E6	4.75
3)5.40	aaa-Trifluorotoluene	411.0	362.4	444.2	425.4	412.4	411.1 E3	7.37
4)7.11	TOLUENE	1.1	1.0	1.1	1.1	1.1	1.1 E6	2.80
5)9.89	ETHYLBENZENE	803.5	768.0	799.2	880.8	841.0	818.5 E3	5.30
6)10.12	M-PXYLENE	1.2	1.1	1.1	1.1	1.1	1.1 E6	4.04
7)10.77	O-XYLENE	1.1	1.0	1.0	1.0	0.9	1.0 E6	7.47
8)11.61	BROMOFLUOROBENZENE	989.4	932.4	911.8	938.1	906.0	935.5 E3	3.53
9)12.73	135-TRIMETHYLBENZENE	848.6	828.5	956.6	1155.2	1111.3	980.0 E3	15.19
10)13.36	124-TRIMETHYLBENZENE	577.4	597.3	714.0	878.9	843.9	722.3 E3	19.08

(#) = Out of Range

PVOC SOIL.M

Mon May 20 16:00:48 1996

[illegible]



IEA

An Aquarion Company

126 West Center Court
Schaumburg, Illinois 60195

Phone 1-800-933-2580
Fax 847-705-1567

May 25, 1996

Burns & McDonnell
Scott Kolb
999 Oakmont Plaza Drive

Westmont, IL 60559

Dear Scott Kolb:

Please find enclosed the analytical results of the samples received at our laboratory on May 03, 1996. This report contains sections addressing the following information at a minimum:

- Definitions
- Analytical Methodology
- State certifications
- Analytical Results
- Chain-of-custody (if applicable)

IEA Project#: L72960732

Client Project: 95-465-4-501

Purchase Order#:

IEA Quote#:


Site:

Copies of this analytical report and supporting data are maintained in our files for three years; samples are retained for two weeks unless special arrangements have been made. Unless specifically indicated, all analytical testing was performed at this laboratory and no portion of the testing was subcontracted.

We appreciate your selection of our services and welcome any questions or suggestions you may have relative to this report. Please contact Jim Dowse at (800) 933-2580 for any additional information. Thank you for utilizing our services, we hope you will consider us for your future analytical needs.

I have reviewed and approved the enclosed data for final release.

Sincerely


Larry D. Lewis
Director of Operations
IEA-Illinois Laboratory





IEA

An Aquarion Company

Definitions of Data Qualifiers

Organic Analysis

- B - This analyte was detected in the method blank associated with this sample. The concentration reported in the method blank is suspected to contribute to the reported concentration of the analyte in the sample.
- E - The concentration reported for this compound exceeds the calibration range of the instrument.
- H - This sample had one or more surrogate recoveries above the acceptance criteria due to coelution with a nontarget compound.
- J - The reported concentration for this compound is an estimated value. When associated with tentatively identified compounds (TICs), the result is quantitated based on a response factor of 1. When the flag is associated with a calibrated target compound, the compound has been positively identified and the reported concentration is above the method detection limit (MDL), but below the practical quantitation limit (PQL).
- L - This sample had one or more surrogate recoveries below the acceptance criteria due to matrix effects. This effect was confirmed through a second analysis of the sample.
- LI - The recovery of the internal standard corresponding to this compound did not meet the acceptance criteria due to matrix effects. This effect was confirmed through a second analysis of the sample.
- T1 - The chromatographic profile of this sample does not match that of a gasoline standard. Another unidentifiable petroleum product is present in this sample. Quantitation is based on a gasoline standard calibration.
- T2 - The chromatographic profile of this sample does not match that of a diesel fuel standard. Another petroleum product is present in this sample. Quantitation is based on a diesel fuel standard calibration.
- U - This compound was not detected in the sample above the PQL.
- UD - This compound was not detected above the elevated PQL in this diluted analysis.

Inorganic Analysis

- E - The reported value was estimated due to the presence of interference.
- M - Duplicate injection precision was not met.
- N - Spiked sample recovery was not within control limits.
- S - The reported value was determined by the Method of Standard Additions(MSA).
- W - Post digestion spike for Furnace AA analysis is out of control limits (85-115%), while sample absorbance is less than 50% of spike absorbance.
- * - Duplicate analysis was not within control limits.
- + - Correlation Coefficient for the MSA is less than 0.995.



IEA

An Aquarion Company

Sample Summary

IEA-Illinois	
Laboratory ID	Client ID
L72960732-001	JLM031-6
L72960732-002	JLM031-1
L72960732-003	JLM030-1
L72960732-004	JLM031-ERB
L72960732-005	TB 5296



**IEA**

An Aquarion Company

Client: **Burns & McDonnell**IEA Job#: **L72960732**Project ID: **95-465-4-501**Matrix: **Soil**Method: **8020A****Purgeable Aromatic Compounds--BTEX****GC Volatiles Analysis****µg/Kg - Dry Weight**

Percent Solids		74%	73%	72%	100%	100%	PQL
Dilution Factor		5	5	1	1	1	
Method Blank		VV050796	VV050796	VV050696	VV050696	VV050796	
Client ID		JLM031-6	JLM031-1	JLM030-1	Method Blank	Method Blank	
Analyte	Lab ID	001	002	003	VV050696	VV050796	
Total Xylenes		460	320	U	U	U	2
Surrogate Recovery		88%	65%	71%	101%	91%	65-135 %
Date Sampled		5/2/96	5/2/96	5/2/96	---	---	
Date Analyzed		5/8/96	5/8/96	5/6/96	5/6/96	5/7/96	

PQL = Practical Quantitation Limit**To obtain the sample-specific quantitation limit, multiply the PQL by the Dilution Factor.**

**IEA**

An Aquarion Company

Client: Burns & McDonnell

IEA Job#: L72960732

Project ID: 95-465-4-501

Matrix: Water

Method: 8020A

Purgeable Aromatic Compounds--BTEX
GC Volatiles Analysis
µg/L

Dilution Factor	1	1	1			PQL
Method Blank	VV050796	VV050796	VV050696			
Client ID	JLM031-ERB	TB 5296	Method Blank			
Analyte Lab ID	004	005	VV050696			
Total Xylenes	U	U	U			2
Surrogate Recovery	99%	101%	101%			75-125%
Date Sampled	5/2/96	5/2/96	---			
Date Analyzed	5/6/96	5/6/96	5/6/96			

PQL = Practical Quantitation Limit

To obtain the sample-specific quantitation limit, multiply the PQL by the Dilution Factor.

Purgeable Aromatics--Xylenes

Matrix Spike/Matrix Spike Duplicate

Matrix: Soil

Date Analyzed: 5/7/96

IEA Sample ID: BATCH MS

Compound	Spike Added (ug/Kg)	Sample Concentration (ug/Kg)	Matrix Spike Concentration (ug/Kg)	% Recovery
Total Xylenes	150	<2	97	65%

Compound	Spike Added (ug/Kg)	Matrix Spike Dup Concentration (ug/Kg)	% Recovery	% Difference
Total Xylenes	150	105	70%	8%

% Recovery Limits: 65-135 %

% Difference Limits: +/- 20 %

Purgeable Aromatics--Xylenes

Matrix Spike/Matrix Spike Duplicate

Matrix: Water

Date Analyzed: 5/7/96

IEA Sample ID: BATCH QC

Compound	Spike Added (ug/L)	Sample Concentration (ug/L)	Matrix Spike Concentration (ug/L)	% Recovery
Total Xylenes	150	<2	153	102%

Compound	Spike Added (ug/L)	Matrix Spike Dup Concentration (ug/L)	% Recovery	% Difference
Total Xylenes	150	153	102%	0%

% Recovery Limits: 75-125%

% Difference Limits: +/- 20 %

Response Factor Report GC

Method : K:\CHEMSTN\GCV\METHODS\CALCURVS\042996.M
 Title : PVOC in Soil; Calib. Date 4/29/96
 Last Update : Mon Apr 29 12:12:54 1996
 Response via : Initial Calibration

Calibration Files

2ppb =GCV5680.D 5 =GCV5681.D 10 =GCV5682.D
 50 =GCV5683.D 100 =GCV5684.D

RT	Compound	2ppb	5	10	50	100	Avg		%RSD

1)2.27	MTBE	548.4	607.6	589.8	575.3	494.5	563.1	E3	7.82
2)3.98	BENZENE	1.5	1.6	1.6	1.6	1.5	1.6	E6	2.62
3)5.40	aaa-Trifluorotoluene	477.2	503.9	507.2	584.9	557.4	526.1	E3	8.33
4)7.11	TOLUENE	1.2	1.3	1.3	1.4	1.3	1.3	E6	6.30
5)9.89	ETHYLBENZENE	779.8	830.3	833.9	940.2	901.7	857.2	E3	7.41
6)10.12	M-PXYLENE	1.1	1.2	1.2	1.3	1.2	1.2	E6	4.66
7)10.77	O-XYLENE	981.5	1040.2	1015.7	1124.2	1072.1	1046.7	E3	5.
8)11.61	BROMOFLUOROBENZENE	773.6	848.2	863.3	1003.3	979.5	893.6	E3	10.73
9)12.73	135-TRIMETHYLBENZENE	747.3	844.4	906.4	1185.1	1186.6	974.0	E3	20.70
10)13.36	124-TRIMETHYLBENZENE	499.4	608.8	627.2	885.4	883.1	700.8	E3	24.90

(#) = Out of Range

042996.M

Mon May 20 16:16:05 1996

Evaluation Continuing Calibration Report

Data File : K:\CHEMSTN\GCV\DATA\QV0539\GCV5825.D Vial: 2
 Acq On : 06 May 96 12:01 PM Operator: JBRIESE
 Sample : CCV#1-BTEXM-50PPB Inst : GCV
 Misc : GCV-0101;VV050696 Multiplr: 1.00

Method : K:\CHEMSTN\GCV\METHODS\CALCURVS\042996.M
 Title : PVOC in Soil; Calib. Date 4/29/96
 Last Update : Mon Apr 29 12:12:54 1996
 Response via : Multiple Level Calibration

	Compound	AvgRF	CCRF	%Diff
1 t	MTBE	563.125	537.590 E3	4.5
2 T	BENZENE	1.578	1.451 E6	8.1
3 S	aaa-Trifluorotoluene	526.128	505.110 E3	4.0
4 T	TOLUENE	1.294	1.216 E6	6.0
5 T	ETHYLBENZENE	857.177	845.971 E3	1.3
6 T	M-PXYLENE	1.188	1.087 E6	8.5
7 T	O-XYLENE	1046.735	941.779 E3	10.0
8 S	BROMOFLUOROBENZENE	893.561	913.193 E3	-2.2
9 T	135-TRIMETHYLBENZENE	973.952	1065.271 E3	-9.4
10 T	124-TRIMETHYLBENZENE	700.770	786.215 E3	-12.2

(#) = Out of Range
 GCV5683.D 042996.M

SPCC's out = 0 CCC's out = 0
 Mon May 20 16:20:14 1996

Response Factor Report G

Method : K:\CHEMSTN\GCV\METHODS\PVOC SOIL.M
 Title : PVOC in Soil; Calib. Date: 5/7/96
 Last Update : Tue May 14 13:26:55 1996
 Response via : Initial Calibration

Calibration Files

2ppb =GCV5853.D 5 =GCV5854.D 10 =GCV5855.D
 50 =GCV5856.D 100 =GCV5857.D

RT	Compound	2ppb	5	10	50	100	Avg RF	%RSD
1)2.27	MTBE	572.5	519.8	343.0	456.7	399.6	458.3 E3	19.98
2)3.98	BENZENE	1.3	1.2	1.2	1.2	1.2	1.2 E6	4.75
3)5.40	aaa-Trifluorotoluene	411.0	362.4	444.2	425.4	412.4	411.1 E3	7.37
4)7.11	TOLUENE	1.1	1.0	1.1	1.1	1.1	1.1 E6	2.80
5)9.89	ETHYLBENZENE	803.5	768.0	799.2	880.8	841.0	818.5 E3	5.30
6)10.12	M-PXYLENE	1.2	1.1	1.1	1.1	1.1	1.1 E6	4.04
7)10.77	O-XYLENE	1.1	1.0	1.0	1.0	0.9	1.0 E6	7.47
8)11.61	BROMOFLUOROBENZENE	989.4	932.4	911.8	938.1	906.0	935.5 E3	3.53
9)12.73	135-TRIMETHYLBENZENE	848.6	828.5	956.6	1155.2	1111.3	980.0 E3	15.19
10)13.36	124-TRIMETHYLBENZENE	577.4	597.3	714.0	878.9	843.9	722.3 E3	19.08

(#) = Out of Range

PVOC SOIL.M

Mon May 20 16:00:48 1996

Evalua Continuing Calibration Report

Data File : K:\CHEMSTN\GCV\DATA\QV0539\GCV5839.D Vial: 18
 Acq On : 06 May 96 08:52 PM Operator: JBRIESE
 Sample : CCV#2-BTEXM-50PPB Inst : GCV
 Misc : GCV-0101;VV050696 Multiplr: 1.00

Method : K:\CHEMSTN\GCV\METHODS\CALCURVS\042996.M
 Title : PVOC in Soil; Calib. Date 4/29/96
 Last Update : Mon Apr 29 12:12:54 1996
 Response via : Multiple Level Calibration

	Compound	AvgRF	CCRF	%Dev
1 t	MTBE	563.125	631.477 E3	-12.1
2 T	BENZENE	1.578	1.641 E6	-4.0
3 S	aaa-Trifluorotoluene	526.128	591.363 E3	-12.4
4 T	TOLUENE	1.294	1.403 E6	-8.4
5 T	ETHYLBENZENE	857.177	915.225 E3	-6.8
6 T	M-PXYLENE	1.188	1.267 E6	-6.7
7 T	O-XYLENE	1046.735	1136.820 E3	-8.6
8 S	BROMOFLUOROBENZENE	893.561	1021.009 E3	-14.3
9 T	135-TRIMETHYLBENZENE	973.952	1196.793 E3	-22.9#
10 T	124-TRIMETHYLBENZENE	700.770	898.668 E3	-28.2#

(#) = Out of Range
 GCV5683.D 042996.M

SPCC's out = 0 CCC's out = 0
 Mon May 20 16:22:55 1996

Request for Chemical Analysis and Chain of Custody Record

[illegible]



IEA
An Aquarion Company

126 West Center Court
Schaumburg, Illinois 60195

Phone 1-800-933-2580
Fax 847-705-1567

May 30, 1996

Burns & McDonnell
Scott Kolb
999 Oakmont Plaza Drive
Westmont, IL 60559

Dear Scott Kolb:

Please find enclosed the analytical results of the samples received at our laboratory on May 06, 1996. This report contains sections addressing the following information at a minimum:

- Definitions
- Analytical Methodology
- State certifications
- Analytical Results
- Chain-of-custody (if applicable)

IEA Project#: L72960749

Client Project: 95-465-4-501

Purchase Order#:

IEA Quote#:

Site:

Copies of this analytical report and supporting data are maintained in our files for three years; samples are retained for two weeks unless special arrangements have been made. Unless specifically indicated, all analytical testing was performed at this laboratory and no portion of the testing was subcontracted.

We appreciate your selection of our services and welcome any questions or suggestions you may have relative to this report. Please contact Jim Dowse at (800) 933-2580 for any additional information. Thank you for utilizing our services, we hope you will consider us for your future analytical needs.

I have reviewed and approved the enclosed data for final release.

Sincerely

Larry D. Lewis
Director of Operations
IEA-Illinois Laboratory





IEA

An Aquarion Company

Definitions of Data Qualifiers

Organic Analysis

- B -** This analyte was detected in the method blank associated with this sample. The concentration reported in the method blank is suspected to contribute to the reported concentration of the analyte in the sample.
- E -** The concentration reported for this compound exceeds the calibration range of the instrument.
- H -** This sample had one or more surrogate recoveries above the acceptance criteria due to coelution with a nontarget compound.
- J -** The reported concentration for this compound is an estimated value. When associated with tentatively identified compounds (TICs), the result is quantitated based on a response factor of 1. When the flag is associated with a calibrated target compound, the compound has been positively identified and the reported concentration is above the method detection limit (MDL), but below the practical quantitation limit (PQL).
- L -** This sample had one or more surrogate recoveries below the acceptance criteria due to matrix effects. This effect was confirmed through a second analysis of the sample.
- LI -** The recovery of the internal standard corresponding to this compound did not meet the acceptance criteria due to matrix effects. This effect was confirmed through a second analysis of the sample.
- T1 -** The chromatographic profile of this sample does not match that of a gasoline standard. Another unidentifiable petroleum product is present in this sample. Quantitation is based on a gasoline standard calibration.
- T2 -** The chromatographic profile of this sample does not match that of a diesel fuel standard. Another petroleum product is present in this sample. Quantitation is based on a diesel fuel standard calibration.
- U -** This compound was not detected in the sample above the PQL.
- UD -** This compound was not detected above the elevated PQL in this diluted analysis.

Inorganic Analysis

- E -** The reported value was estimated due to the presence of interference.
- M -** Duplicate injection precision was not met.
- N -** Spiked sample recovery was not within control limits.
- S -** The reported value was determined by the Method of Standard Additions(MSA).
- W -** Post digestion spike for Furnace AA analysis is out of control limits (85-115%), while sample absorbance is less than 50% of spike absorbance.
- * -** Duplicate analysis was not within control limits.
- + -** Correlation Coefficient for the MSA is less than 0.995.

